



LEGEND

DESIGN COUNTOURS - INTERVAL = 0.1m

150mm KERB AND GUTTER. REFER DPTI DRG S-0370 SHEET 7 FOR DETAILS.

NEW STORMWATER PIPE. REFER SHEET 4 FOR DETAILS.

NEW SEWER PIPE ALIGNMENT. COUNCIL TO UNDERTAKE WORKS IN ADVANCE OF THE SHARED PATH WORKS.

LANDSCAPING MULCH AREA TO COUNCIL/WALLIS SPECIFICATIONS.

REMOVE EXISTING CHAIN MESH FENCE AND FOOTINGS BETWEEN MATCHLINE POINTS.

CONNECT TO EXISTING SHUTE # 8060 DRAIN TO NEW FIELD GULLY WITH 100 DIA SEWER GRADE PIPE AT 1% MINIMUM GRADE. PROVIDE A STORMWATER INSPECTION OPENING. REFER SMD-01 FOR DETAILS.

100mm THICK, 6m LONG CONTINUOUS LINE TO EXISTING AND NEW PATH.

NEW FENCE CONSTRUCTION ALONG PATH TO BE HARDWOOD POSTS WITH 150mm HIGH SWIRLING POOL STYLE PANELS. REFER SUPERINTENDENT FOR DETAILS.

100mm THICK, 6m LONG CONTINUOUS LINE TO EXISTING PATH.

RELOCATED CWMS WORKS TO BE UNDERTAKEN BY OTHERS.

1 IN 2.5 BATTER MAX

1 IN 5 BATTER

1 IN 5 BATTER

1 IN 5 BATTER

1200mm LONG LANDING

EXISTING FLOOD LIGHT. LOCALLY ADJUST EASTINGWORKS TO SUIT.

BATTER SLOPE TO BE ADJUSTED TO SUIT THE EXISTING BACK OF KERB. BATTER TREATMENT TO BE GRouted ROCK.

TO MOUNT BARKER DISTRICT COUNCIL'S LANDSCAPE CONSULTANT'S LANDSCAPE

EXISTING SHARED PATH

EXISTING SHARED PATH TO MATCH TO EXISTING DRIVEWAY PAVEMENT LEVELS

TO SOUTH EASTERN FREEWAY

MAIN STREET

ADELAIDE ROAD

DEVELOP EXISTING HEADWALL. CONNECT EXISTING PIPE TO NEW 150 KERB AND GUTTER. NEW PIPE EXTENSION DIAMETER TO MATCH EXISTING.

EXISTING SEP TO BE DEMOLISHED ASSOCIATED PIPING WORK TO BE REMOVED TO BE PAST THE EXTENT OF WORKS. PROVIDE CONCRETE PLUG TO PIPE END.

EXISTING BOLLARDS TO BE REMOVED. EXISTING CARP SIGNAGE TO BE REINSTATED TO MATCH NEW LEVELS AT COMPLETION OF WORKS.

MATCH TO EXISTING UPRIGHT KERB

MATCH NEW FENCE TO EXISTING FENCE

MATCH TO EXISTING UPRIGHT KERB

DEMONISH EXISTING HEADWALL. CONNECT EXISTING PIPE TO NEW 150 KERB AND GUTTER. NEW PIPE EXTENSION DIAMETER TO MATCH EXISTING.

EXISTING SEP TO BE DEMOLISHED ASSOCIATED PIPING WORK TO BE REMOVED TO BE PAST THE EXTENT OF WORKS. PROVIDE CONCRETE PLUG TO PIPE END.

EXISTING BOLLARDS TO BE REMOVED. EXISTING CARP SIGNAGE TO BE REINSTATED TO MATCH NEW LEVELS AT COMPLETION OF WORKS.

GENERAL NOTES:

- CONTRACTOR TO CONFIRM LOCATION AND DEPTH OF ALL EXISTING SERVICES PRIOR TO CONSTRUCTION AND REPORT ANY CONFLICT ISSUES WITH THE NEW DESIGN TO THE SUPERINTENDENT.
- DURING CONSTRUCTION CONTRACTOR TO TAKE CARE WITH TREE ROOTS. TREE ROOTS GREATER THAN 200mm DIAMETER REQUIRE SUPERINTENDENT APPROVAL TO CUT.
- ANY IRRIGATION INFRASTRUCTURE TO BE REINSTATED. REFER SUPERINTENDENT FOR NEW LOCATION.
- THERE IS THE PRESENCE OF UNDERGROUND ELECTRICAL IN THE VICINITY DUE TO EXISTING FLOOD LIGHT. DIALBAUDING INVESTIGATION DID NOT INDICATE THE LOCATION OF ANY UNDERGROUND ELECTRICAL IN THE AREA. CONTRACTOR TO ENSURE ELECTRICAL IS MADE SAFE PRIOR TO EXCAVATION. CONNECTION TO BE REINSTATED.
- REINSTATE ALL LIMEPAVING THAT IS DISTURBED OR REMOVED DURING CONSTRUCTION. IN ACCORDANCE WITH ASTRA MANUAL OF URBAN TRAFFIC CONTROL DEVICES.
- RE-VEGETATION OF BATTERS IN THE GRASSED AREAS TO BE IN ACCORDANCE WITH MOUNT BARKER DISTRICT COUNCIL STANDARDS AND REQUIREMENTS. REFER SECTION 5.2 GRASSING DESIGN, CONSTRUCTION AND DEVELOPMENT OF INFRASTRUCTURE ASSETS STANDARDS AND REQUIREMENTS.
- CONTRACTOR TO MINIMIZE IMPACTS TO EXISTING TREES WITHIN THE TREE CANOPY AREAS.
- SHARED PATH PAVEMENT TO BE SUPPLIED BY MOUNT BARKER DISTRICT COUNCIL.
- ROCK FILLED GARDEN RETAINING WALLS BASKET AND ROCK TYPE TO BE SPECIFIED BY SUPERINTENDENT.
- NEW SHARED PATH LIGHTING TO MATCH EXISTING STANDARDS. LOCATION OF NEW LIGHTS AND CONDUITS TO BE CONFIRMED. DESIGN NOT PART OF THIS WORKS.

EXISTING SERVICES LEGEND

	APPROXIMATE LOCATION OF EXISTING OVERHEAD ELECTRICAL
	APPROXIMATE LOCATION OF EXISTING UNDERGROUND ELECTRICAL
	APPROXIMATE LOCATION OF EXISTING GAS
	APPROXIMATE LOCATION OF EXISTING STORMWATER
	APPROXIMATE LOCATION OF EXISTING WATER

THIS DRAWING IS TO BE VIEWED IN COLOUR AS SOME FEATURES / SYMBOLS ARE DIFFERENTIATED BY COLOUR. DRAWING NOT TO BE RELIED ON IF PRINTED IN GREYSCALE.

REV	AMENDMENT / REASON FOR ISSUE	DATE	DES.	DWN.	DWGCHK.	VERIFIED	APPROVED
2	ISSUED FOR TENDER	21.12.17	AGM	AGM	PZ		
1	ISSUED FOR COMMENT	05.12.17	AGM	AGM	PZ		

PUBLIC UTILITIES:
THE SERVICES SHOWN ARE DERIVED FROM PLANS OBTAINED FROM THE RELEVANT SERVICE AUTHORITIES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ARRANGE WITH THE RELEVANT SERVICE AUTHORITIES FOR CONFIRMATION OF SERVICES AND THEIR LOCATION BEFORE EXCAVATION WORK COMMENCES.

100mm ON ORIGINAL DRAWINGS - DO NOT SCALE DRAWING

www.tonkin.com.au

PRELIMINARY	
SHEET SIZE	A1
SCALE	1:200
ORIGINAL SURVEY BY	MOUNT BARKER DISTRICT COUNCIL
ADELAIDE ROAD SHARED PATH GENERAL CONSTRUCTION PLAN	
FILENAME:	2010722_SHEET 01.DWG
JOB NUMBER	20170722
SHEET NUMBER	1
REVISION	1